

കില - Entire building networking with sufficient nodes (LAN Cabling and Fibre Connectivity) - ജോലികൾ ചെയ്യുന്നത് സംബന്ധിച്ച്

കാട്ടേഷൻ നോട്ടീസ്

കില ക്യാമ്പസിൽ പ്രവർത്തിച്ചു വരുന്ന അർബൻ പോളിസി കമ്മീഷൻ ഓഫീസിലേക്ക് ആവശ്യമായ Entire building networking with sufficient nodes (LAN Cabling and Fibre Connectivity) ജോലികൾ ചെയ്യുന്നതിന് അംഗീകൃത സപ്ലൈയർ/ഡീലർമാരിൽ നിന്നും കാട്ടേഷനുകൾ ക്ഷണിക്കുന്നു.

മുദ്ര വച്ച കാട്ടേഷനുകൾ **ഡയറക്ടർ, കേരള ഇൻസ്റ്റിറ്റ്യൂട്ട് ഓഫ് ലോക്കൽ അഡ്മിനിസ്ട്രേഷൻ (കില), മുളങ്കുന്നത്തുകാവ്, തൃശ്ശൂർ 680 581** എന്ന വിലാസത്തിലോ കില തൃശ്ശൂർ ഓഫീസിൽ നേരിട്ടോ **18.01.2025 (ശനിയാഴ്ച) ഉച്ചയ്ക്ക് 02.00 മണിക്കകം** എത്തിക്കേണ്ടതാണ്. ലഭ്യമായ കാട്ടേഷനുകൾ അന്നേദിവസം വൈകീട്ട് **03.30 ന്** ഹാജരായവരുടെ സാന്നിധ്യത്തിൽ തുറക്കുന്നതാണ്. കാട്ടേഷനുകളിൽ അന്തിമ തീരുമാനം എടുക്കുന്നതിനും റദ്ദ് ചെയ്യുന്നതിനുമുള്ള അധികാരം ഡയറക്ടർ ജനറലിൽ നിക്ഷിപ്തമാണ്.

Entire building networking with sufficient nodes (LAN Cabling and Fibre Connectivity) ജോലികൾ ചെയ്യുന്നതിനുള്ള (ആവശ്യമായ സാധനങ്ങളുടെ വിലയും, പണിക്കൂലി ഉൾപ്പെടെയുള്ള തുക) ജി.എസ്.ടി ഉൾപ്പെടെയുള്ള തുകയാണ് രേഖപ്പെടുത്തേണ്ടത്. കാട്ടേഷനുകൾ അംഗീകരിക്കുന്ന പക്ഷം Entire building networking with sufficient nodes (LAN Cabling and Fibre Connectivity) എന്നീ ജോലികൾ ഓഫീസിൽ നിന്നും സപ്ലൈ ഓർഡർ ലഭ്യമാകുന്ന മുറയ്ക്ക് സമയബന്ധിതമായി ചെയ്യേണ്ടതും പ്രവർത്തനക്ഷമമാക്കേണ്ടതുമാണ്.

Entire building networking with sufficient nodes (LAN Cabling and Fibre Connectivity) സ്പെസിഫിക്കേഷൻ ചുവടെ ചേർക്കുന്നു.

TECHNICAL SPECIFICATION

Sl no	Product / Work Name	Remarks if Any	Quantity / Approx Meter
1.	24 port 10/100/1000 Unmanaged Switch with minimum 2 port SFP (24+2or4)	D-Link / Tp-Link	1 Nos
2.	Horizontal Network Cable Manager for Managing Cables to a 24-port network switch in Network Rack		1 Nos
3.	D-Link Cat6 UTP 24 Port Loaded Patch Panel		1 Nos
4.	6U Network Rack		1 Nos
5.	CAT 6 UTP Cable	Brand: D-Link /Finolex / Molex	Minimum 100 Meter (Per Meter Charges to be Quoted, Payment will be made on Actual

Draft #103 of File 2022/6786/HQ. Approved by Director General on 26-Dec-2024 07:47 AM - Page 1

			Basis)
6.	Wiring Charges for CAT 6 Cable Using Sufficient Casing Capping and other accessories		Minimum 100 Meter (Per Meter Charges to be Quoted, Payment will be made on Actual Basis)
7.	Cat 6 Keystone Jack + Gang Box + Single / Dual Port Faceplate	Brand Dlink or Equivalent	Minimum 16 Nos (Per Set Charges to be Quoted, Payment will be made on Actual Basis)
8.	Per Socket Charges for Fixing and testing Network Keystone Jack + Gang Box + single /dual port Face Plate and other Consumables If any used for fixing.		16 Nos (Per item fixing Charge to be Quoted. Payment will be made on Actual Basis)
9.	D Link CAT 6 Patch Cord 0.5MTR		20 Nos (Per Item Charge to be Quoted)
10.	D Link CAT 6 Patch Cord 2 MTR		20 Nos (Per Item Charge to be Quoted)
11.	D-LINK [DEM-310GT]1000BASE-LX Single-Mode 10 Km LC SFP Transceiver		2 Nos (Per Item Charge to be Quoted)
12.	6 Core Armoured Fibre Cable	Brand: Dlink	Minimum 50 Meter (Per Meter Charges to be Quoted, Payment will be made on Actual Basis)
13.	HDPE Pipe		Approx 30 Meter (Per Meter Charges to be Quoted, Payment will be made on Actual Basis)
14.	Laying Charges for Fibre Cable using Sufficient Accessories and Splicing / Terminating of Optical Cable Using Necessary PVC Boxes and other Cables and Connectors		Lumpsum Amount
15.	3 Pin 6 Amp Socket with Open BOX, Face Plate etc of same brand (Brand: GM / Gold Medal)		Minimum 3 Nos (Per Set Charge to be Quoted)
16.	1.5SQMM Wire – V Guard		Approx. 50 Metre (Per Meter Charges to be Quoted, Payment will be

			made on Actual Basis)
17.	Laying Charges off Electric Cable using CASING Capping (1.5SQMMx3)		Lumpsum Amount
18.	Installation, Fixing, Terminating and Testing Charges of Network Rack with all consumables and Items (Network Switches, Patch Panels, Cable Managers SFPs, Media Converters, Splicing, Crimping, Punching, Charges for Fibre Patch cords, etc)		Lumpsum Amount

* This is a computer generated document. Hence no signature is required.